

# NED UNIVERSITY OF ENGINEERING & TECHNOLOGY



University Road, Karachi 75270.

Tel: 9926 1261-68 Ext 2471 & 2291

Fax: 9926 1255 Email: dp@neduet.edu.pk

Web: www.neduet.edu.pk

Director Procurement

No. PC/NEDD/143446/7047/3896

Dated: 24.05.2021

## **CORRIGENDUM**

TENDER NO. PC/NED/RGT/  
Renovation/7047/2021  
Dated: 06.05.2021

Renovation of Building for  
Establishment of Civil Engineering  
Program at TIEST, Tharparkar  
Campus.

With reference to above Tender Notice published in Newspapers on 09.05.2021 with INF-KRY/1630/21, all concerned are informed that some corrections have been made in BoQ items of the subject tender. Complete details of these corrections are available at NEDUET & SPPR Websites. However, all other terms & conditions of the tender will remain the same.

**Director Procurement**

INF-KRY: 1862/21

ہم دہشگر دی کے خلاف متحد ہیں

**Say No to Corruption**

Sub: Renovation of Building for Establishment of Civil Engineering Program at TIEST

BoQ Items – Electrical Works		
BOQ Item No.	Present Specification	Revised Specification
3	<p>Wall mounted, 18 SWG MS Sheet make powder coated with lock front safety plate internal wiring with heavy Neutral and Earth terminal, MCCB of Terasaki make comprising of following rating:</p> <p>40A, Model:XE100CB, 2.5 KA/1.3 KA, Three Pole, MCCB, 01 No. 20A, Model: TB-5S, 06 KA, Single Pole, MCCB, 09 Nos. Indicating Lamp 03 Nos.</p>	<p>Providing, Installation, testing &amp; Commissioning of Wall Mounted open type Main Distribution Board made of 18 SWG MS Sheet casing, complete with door, locking arrangement, front safety plate, internal wiring, Cu. Lugs, bus bars (earth &amp; Neutral Terminal 100A) and painted with off-white powder coated paint, having enough space as shown in drawing D.B will have all MCCB of Terasaki Malaysia/Legrand France/ABB Germany or equivalent make and comprising of</p> <p><b>Incoming:</b></p> <p>250A/19KA TPN MCCB E 250SF (COS) 02 Nos                      Indicating Lamps LED type 06 Nos                      Digital Am meter + Volt meter with 5A ct. set 01 No</p> <p><b>Outgoing:</b></p> <p>400ATPN Cu Bus bar 05 Nos                      40A/5KA TP MCCB XE 100NS 01 No                      40A/5KA TP MCCB XE 100NS 06 No                      30A/6KA DP-TB MCCB TB 5S 02 Nos</p> <p>Complete in all respect as per drawing and as required &amp; approved by the Engineer/Directorate of Works &amp; Services.</p>
	<b>Present Quantity</b>	<b>Revised Quantity</b>
15	2,000	130